



FERTILISERS AND CHEMICALS TRAVANCORE LTD

CLARIFICATIONS ON QUERIES RAISED BY BIDDERS

CORRIGENDUM

NAME OF THE WORK:- Re Location of Raw Water Pipe Line Passing Through New NP Plant At FACT CD, Ambalamedu, Kochi, Kerala.

Tender No: 04031/2022-2023/E26729

Tender ID: 2023_FACT_738222_1

	Queries Raised by bidders	FACT Reply
1	As per the BOQ item 13, RCC quantity is 6 m ³ and the quantity of the tore steel as per BOQ item 17 is 3800 Kg, which is required or not.	M30 concrete (BOQ item no. 13) is for casting pipe sleepers. Nominal mix concrete (Item no.12) is for pipe crossing under the proposed new road (by others) which may or may not be executed based on the depth of raw water line from the proposed road surface. Hence steel consumption (Item no. 17) may or may not be executed to full quantity.
2	For the BOQ item No-18 the supply of MS insert plates are included in contractors scope or you will supply.	Supply of all materials to be used for construction are under the scope of contractor. (See clause 3.2 and clause 4 of document 32687-12-DA-005 R1, page 2 of 4)
3	For the BOQ item No-18 the supply of MS pipes is in contractor's scope or not, and the size of pipe is not mentioned, and supply of paint also in contractor's scope or not.	See document/drawing- 32687-12-DG-00003 R1 for details of pipe (BOQ item no. 19). Supply of pipes and paint are under the scope of the contractor.
4	The Third Party inspection (TPI) is only visual inspection with MTC of materials. Please confirm.	All mandatory tests as per the standard specified shall be followed.
5	For the NDT, the DP Test and UT are considered which is to be confirm.	DP test and UT are confirmed
6	Material supply as per the BOQ should be paid fully as per the payment terms, whether the same is erected or not.	Material supply as per BOQ will be paid as per the payment terms specified in the tender.
7	Dismantling of the existing line is not in the scope of work	Dismantling of the existing line is not in the scope of contractor.