



27.10.2025

Name of Work: Painting of Phosphoric Acid Storage Tanks (T-1201 D/E) – 2 Nos, Willingdon Island, Kochi.

E-Tender ID No: 2025_FACT_879012_1

Corrigendum(Technical)

CLARIFICATIONS ON PRE-BID QUERIES RAISED BY BIDDERS ARE ATTACHED.

ALL OTHER TERMS AND CONDITIONS SHALL REMAIN UNCHANGED.

Amrutha Terence
Officer(Des)Mat-C

 FACT	FERTILISERS AND CHEMICALS TRAVANCORE LTD
	CLARIFICATIONS ON QUERIES RAISED BY VENDORS

Name of Work: Painting of Phosphoric Acid Storage Tanks (T-1201 D/E) – 2 Nos, Willingdon Island, Kochi.

Tender ID: 2025_FACT_879012_1

Queries raised by bidders

SL NO	QUERY DESCRIPTION	CLARIFICATION TO QUERY
1	Area to be painted as well as the structural painting area	Approximate area to be painted is 1150 m² per tank, which includes the shell and roof areas. The vendor shall carry out structural painting as per the attached General Arrangement Drawing.
2	As per the tender, the finish paint for roof structure, platform, handrail posts, railings, ladders and stairway is specified as epoxy based paint over alkyd primer. However, the epoxy paint is not compatible with alkyd primer. Please specify more details regarding chequered plate finish paint.	Painting Specification for Chequered Plate • Primer: A04 – Alkyd High Build Zinc Phosphate Primer • Finish Paint: F03 – Alkyd Anti skid Abrasion Resistant Synthetic Floor Paint Painting Specification for Stairway, Platforms, Handrails, and Roof Structures • Primer: A02 – Epoxy-Based Zinc Phosphate Primer • Finish Paint: B01 – Epoxy-Based Enamel Paint All dry film thickness (DFT) values shall be as specified in the approved painting specification.
3	Extension of contract period.	Completion time for painting is revised to 40 days from 20 days.