

# TECHNICAL CORRIGENDUM

## CORRIGENDUM FOR PREPARATORY CIVIL WORKS FOR THE CONSTRUCTION OF NEW 10000 MT AMMONIA STORAGE TANK & ALLIED STRUCTURES AT FACT CD – LAND DEVELOPMENT WORKS

1. TPS No 32686-12-PS-004 \_R1, Technical Document No.32686-12-DA-006\_R0 page 1 of 3 of Specific Requirements of Work, Description under the heading – 3. Scope of Work

*“Non explosive demolition of hard rock using chemical cracking agent and removal of hard rock layer up to the required level”.*

*The above clause sentence have been modified as.*

“Non Explosive excavation / demolition of hard rock using Chemical cracking agent / Wire saw cutting or equivalent and removal of hard rock layer up to the required finished ground level of +4.5m”.

**\* The above modification is also applicable on scope of work mentioned in Schedule A and Schedule Q1.**

2. TPS No 32686-12-PS-004\_R1, Technical Document No.32686-12-DA-007\_R1 page 6 of 7 of Engineering Specification- Site Levelling & Rock Cutting Works, Description under the heading – 5.ROCK EXCAVATION WITH NON EXPLOSIVE DEMOLITION AGENTS.

*Additional sentence have been added after paragraph one as.*

“Rock Excavation can also be done through other means of Non explosive methods like Wire saw cutting or equivalent”.

### GENERAL

The proposed Rock cutting/ excavation work is part of land development work for setting up of 10000 MT Ammonia Tank which is to be commenced in two months as per the Capex Work schedule.

As the work is very urgent, period of completion of work cannot be increased.

The Bidder have the permission to work in all shifts 24X7. The bidder may engage necessary Manpower and machinery to complete the work in two months.