

21.01.2025

Name of Work: Civil and Electrical Maintenance Works in FACT Engineering Works (FEW), Palluruthy.

E-Tender ID No: 2025_FACT_842901_1

Corrigendum (Technical)

The item descriptions for line items 1 and 2 in the BOQ and unpriced bid have been revised as follows:

Items No.1 - Handling of furnitures and files inside the rooms

Scope of work includes:

- Relocating the furnitures and files inside the rooms to a suitable location instructed by engineer-in-charge prior to commencement of civil works.
- Returning the furnitures and files to its original location after the completion of the civil works.
- Necessary riggers and helpers required for the relocation works of furnitures and files shall be in scope of contractor.

Entire works shall be done as per special conditions of contract, general conditions of contract and as per instructions of engineer-in-charge

Item No.2 - Removing old & damaged cement plastering on walls

Scope of work includes:

- Removing & securing the power/ data cables & water pipe lines routed over the walls prior to removing the old and damaged cement plastering.
- Chipping & removing old and damaged cement plastering on walls.
- Raking/ pointing out the existing brick-mortar joints.
- Preparing the wall surface for re-plastering.
- Disposing the debris at a location as instructed by engineer-in-charge.

Entire works shall be done as per special conditions of contract, general conditions of contract and as per instructions of engineer-in-charge.

THERE IS NO CHANGE IN THE UNIT AND QUANTITY OF LINE ITEM 1 & 2

ALL OTHER TERMS AND CONDITIONS SHALL REMAIN UNCHANGED.

Amrutha Terence
Officer(Des)Mat-C