

TECHNICAL CORRIGENDUM

Ref: Tender ref no.03017/2021-2022/E 23512 for installation and commissioning of CT, PT in 110 KV substation as part of open access in FACT-UC.

1. **Sub-Clause 3 of Clause 4-‘Other Conditions’ in Schedule Q1**(Clause 3 of special terms and conditions) is modified as below;

The work shall be carried out in two phases. First phase consists of installation of 3nos. current transformers, 3 nos. potential transformers, relocation of isolator and lightning arrester of Feeder-1 and second phase for feeder-2. Each phase work is to be completed within **30 days**. i.e the time required to switch OFF one feeder and switching ON back after work shall be limited to **30 days**. The whole work shall be completed within **90 days** from the date of issuing clearance to start work.

2. **Sub-Clause 7 of Clause 5- ‘Materials’ in Schedule Q1** (Clause 7 of special terms and conditions- materials.) is modified as below;

All necessary civil and mechanical works like rigging/ drilling/cutting/welding are also under contractor's scope. **Before commencement of civil works, 40mm metal in specified yard work area has to be removed and stacked at a nearby location by the contractor as instructed by engineer-in-charge. After completion of the work, metal has to be filled back by the contractor.**