



29.09.2025

Name of Work : Civil and piping works for residual engineering - New Phosphoric acid tanks at Q10 berth, Willingdon Island.

E-Tender ID No : 2025_FACT_877457_1

Corrigendum -Technical

Item no. 61 in BOQ and unpriced bid shall be read as-

“C.1.2 - HEAT TREATMENT AND TESTS - DP / MP TEST

Radiography / Ultrasonic / Dye penetrant / Magnetic Particles inspection of the weld joints shall be conducted as per the code, specs. Drawings & instruction of the Engineer-in-charge. However the extent of inspection (%) shall be as per attached document REF:25ES205.

The rate quoted shall be inclusive of all operations necessary to fulfill the work of radiography (x-ray / gamma ray) ultrasonic, DP/MP tests including all tools / tackles, films, chemicals etc. complete. After testing, if any joint is found defective, the same shall be rectified and re-tested free of cost.

The pay quantity shall be linear centimeters of weld successfully passed.”

All other terms and conditions remains unchanged.

Anand S
DM(Mat)-F